

1 LIFE SAFETY PLAN
SCALE: 1/8" = 1'-0"

1 HOUR FIRE RATED WALL

Accessible Clearance Legend

- (A) **DOOR MANEUVERING SPACE:** FRONT APPROACH, PUSH SIDE CLEAR FLOOR SPACE = DOOR WIDTH x 48" + 2" BEYOND DOOR WIDTH AT LATCH SIDE WHEN DOOR HAS LATCH AND CLOSER
- (B) **DOOR MANEUVERING SPACE:** FRONT APPROACH, PULL SIDE CLEAR FLOOR SPACE = DOOR WIDTH + 18" x 60"
- (C) (1) **DOOR MANEUVERING SPACE:** HINGE SIDE APPROACH, PUSH SIDE CLEAR FLOOR SPACE = DOOR + 22" x 42". PUSH SIDE CLEAR FLOOR SPACE = DOOR + 22" x 4'-0" (WHEN DOOR HAS LATCH AND CLOSER)
- (D) (3) **DOOR MANEUVERING SPACE:** HINGE SIDE APPROACH, PULL SIDE CLEAR FLOOR SPACE = DOOR WIDTH + 42" x 54" ALTERNATIVE PERMISSIBLE CLEAR FLOOR SPACE = DOOR WIDTH + 36" x 60"
- (E) (2) **DOOR MANEUVERING SPACE:** LATCH SIDE APPROACH, PUSH SIDE CLEAR FLOOR SPACE = DOOR WIDTH + 24" x 42" PUSH SIDE CLEAR FLOOR SPACE = DOOR WIDTH + 24" x 48" (WHEN DOOR HAS CLOSER)
- (F) (2) **DOOR MANEUVERING SPACE:** LATCH SIDE APPROACH, PULL SIDE CLEAR FLOOR SPACE = DOOR WIDTH + 24" x 48" PUSH SIDE CLEAR FLOOR SPACE = DOOR WIDTH + 24" x 54" (WHEN DOOR HAS CLOSER)
- (G) **AREA OF REFUGE:** 30" x 48" CLEAR FLOOR SPACE
- (H) **TURNING SPACE:** 5'-0" DIAMETER TURNING AREA (T-SHAPED SPACE ALSO ALLOWED PER ACCESSIBILITY REQUIREMENTS)
- (J) **ACCESSIBLE ROUTE:** 36" WIDE AISLE x LENGTH OF ACCESSIBLE PIECE OF EQ. OR FURNITURE (48" MIN.)
- (K) **WATER CLOSET CLEARANCE:** 56" x 60"
- (L) **CLEAR DECK SPACE:** PARALLEL TO POOL LIFTS 36" X 48"
- (M) **WATER CLOSET CLEARANCE:** 59" x 60" (FLOOR MOUNTED IN A COMPARTMENT)
- (N) **CLEAR FLOOR SPACE:** FRONT OR SIDE APPROACH 30" x 48"

CLEAR FLOOR SPACE — DESIGNATED REQUIRED CLEARFLOOR SPACE (CFS) PER ACCESSIBILITY REQUIREMENTS. REFER TO DIAGRAM ON THIS SHEET AND TO APPROACH CLEARANCES. VERIFY REQ. CLEAR FLOOR SPACE FOR ALL ACCESSIBLE EQUIPMENT, FURNITURE AND AREAS REQUIRED TO BE ACCESSIBLE.

NOTE:

1. 36" MIN. WIDE ACCESSIBLE ROUTE
2. ARRANGE / MAINTAIN MOVABLE FURNITURE SO AS TO PROVIDE AN ACCESSIBLE ROOUTE THROUGH ALL AREAS USED BY OCCUPANTS

SYMBOL	DESCRIPTION
	EXIT SIGN - SHADING INDICATES LIGHTED FACE. ARROW INDICATES EXIT DIRECTION
A	SYSTEM SMOKE DETECTOR
F	SYSTEM FIRE ALARM PULL STATION
P/S	SYSTEM FIRE ALARM HORN / STROBE
P/S WP	SYSTEM FIRE ALARM HORN / STROBE WEATHERPROOF
FACP	FIRE ALARM SYSTEM CONTROL PANEL

GENERAL NOTES

ALTHOUGH DRAWINGS ARE DRAWN TO SCALE, THE ACCURACY OF THE DRAWING CANNOT BE GUARANTEED. ALL DIMENSIONS SHOULD BE DERIVED FROM DIMENSIONED PLANS.

ALL DIMENSIONS, ROUGH OPENING SIZES, AND ELEVATIONS MUST BE VERIFIED IN THE FIELD BY THE GENERAL CONTRACTOR. MAUST ARCHITECTURAL SERVICES CANNOT BE HELD RESPONSIBLE FOR ANY DISCREPANCIES THAT ARE NOT BROUGHT TO THEIR ATTENTION PRIOR TO CONSTRUCTION.

MAUST ARCHITECTURAL SERVICES
DIVISION OF L.E.M., INC.
112 NORTH MAIN STREET
GOSHEN, INDIANA 46526
* Architects
* Planners
* Consultants
* Construction Mgmt.
* Rule 5 and MS4 Filing
PHONE (574) 537-8500
FAX (574) 537-0808

These drawings are the property of Maust Architectural Services and may not be reproduced, copied or reused in any manner without the expressed written consent of Maust Architectural Services.

SSC CONSTRUCTION
Serving Indiana, Illinois, Wisconsin, Michigan, Ohio and Arizona

MERRILLVILLE SCHOOL
8705 MERRILLVILLE RD.
MERRILLVILLE, IN. 46410

REVISIONS:

DATE:
JOB NO.: MAS-17-136
NAME: LIFE SAFETY PLAN
SHEET: LS101