SYMBOLS	DESCRIPTIONS	CATALOG NUMBER	MANUFACTURER	LAMP TYPE	WATTAGE	LUMENS	VOLTAGE
F1 2g	FLUORESCENT LUMINAIRE PER LUMINAIRE SCHEDULE						
	LIGHTING FIXTURE: F1 INDICATES FIXTURE TYPE 2 INDICATES CIRCUIT NUMBER g INDICATES SWITCH CONTROL						
$2b	SINGLE POLE SWITCH - NUMBER INDICATES CIRCUIT, LETTER INDICATES SWITCHING CONTROL.						
$2b 3W	THREE WAY TOGGLE SWITCH -NUMBER INDICATES CIRCUIT, LETTER INDICATES SWITCHING CONTROL.						
	2'X4' RECESSED LED LIGHT	BL50-TR24-36IWCCKD5 (5000K) / LITHONIA 2BLT4 40L ADP LP840	BRITELITE SOLUTIONS / LITHONIA	LED	36 34	4500 4032	120V
P	8" DOWN LIGHT	PLT 90995 (5000K)	PLT	LED	30	2350	120V
F	8" RECESSED LED CAN LIGHT	PLT 90995 (5000K)	PLT	LED	30	2350	120V
F1	6" RECESSED LED CAN LIGHT	PLT 91004 (5000K) / LITHONIA WF6 LL LED 4000K M6	PLT / LITHONIA	LED	15 13	1100 850	120V
	4' LED TUBE DOWN LIGHT	ATG LIFI-35-4FT-G2 40WT (4000K)	ATG	LED	50	4800	120V
	WALL PACK LIGHT	MESTER MEDIUM WALLPACK / LITHONIA TWR1 LED 2 50K MVOLT PE M2	MESTER LIGHTING / LITHONIA LIGHTING	LED	45 41	3800 3527	120V
	EXIT SIGN - SHADING INDICATES LIGHTED FACE. ARROW INDICATES EXIT DIRECTION	LITHONIA EXR LED M6	LITHONIA LIGHTING	LED	1		120V
	WALL MOUNTED EMERGENCY BATTERY LIGHTING FIXTURE	LITHONIA EU2 LED M12	LITHONIA LIGHTING	LED	3.6	44	120V
E	2'X4' RECESSED LED LIGHT WITH IN BUILT BATTERY E INDICATES EMERGENCY LIGHT FIXTURE	BL50-TR24-36IWCCKD5 (5000K) / LITHONIA 2BLT4 46L ADP EL14L LP850	BRITELITE SOLUTIONS / LITHONIA	LED	36 38	4500 4520	120V
	ABOVE DOOR DOWN LIGHT	BRITELITE 24W CUTOFF WALL PACK / LITHONIA OLWX1	BRITELITE SOLUTIONS / LITHONIA	LED	24 20	2400 2693	120V
2x8	TRACK LIGHTS	LITHONIA LTH9000 / LITHONIA SHDE	LITHONIA	LED	17	1200	120V
RLX	EXTERIOR REMOTE PATH LIGHT	EXITRONIX LEDRX-2-GR LED LITHONIA WLTU-LED	EXITRONIX LITHONIA	LED LED	3.7 3.7	44 44	120V
	AIR CIRCULATING FANS						

LIGHTING FIXTURE SCHEDULE

1. FOR DINING HALL PROVIDE DIMMING SYSTEM, LUTRON OR APPROVED EQUAL, TO CONTROL AND DIM ALL FIXTURES IN ROOM. DIMMING SYSTEM SHALL BE COMPATIBLE WITH LED DRIVERS OF FIXTURES. SUBMIT SHOP DRAWINGS INDICATING COMPATIBILITY FOR APPROVAL PRIOR TO PURCHASE.

2. FOR PRAYER HALL PROVIDE DIMMING SYSTEM, LUTRON OR APPROVED EQUAL TO CONTROL AND DIM CAN LIGHTS AND 4' TUBE LIGHTS INDEPENDENTLY OF EACH OTHER, FOR ALL FIXTURES IN ROOM. DIMMING SYSTEM SHALL BE COMPATIBLE WITH LED DRIVES OF FIXTURES. SUBMIT SHOP DRAWINGS INDICATING COMPATIBILTY FOR APPROVAL PRIOIR TO PURCHASE.

3. WIRE ALL LIGHT FIXTURES AS PER CIRCUITING SHOWN, AND PER PANEL SCHEDULE ON DRAWING E301.

4. FOR SITE LIGHTING REFER TO CIVIL DRAWING C8.0. ELECTRICAL CONTRACT SHALL COORDINATE WITH CIVIL CONTRACTOR. CIVIL CONTRACTOR SHALL FURNISH AND ISTALL UNDERGROUND CONDUIT, HAND HOLES, AND POLE BASES. ELECTRICAL CONTRACTOR SHALL FURNISH AND INSTALL WIRING POLES AND LIGHT FIXTURES. ELECTRICAL CONTRACTOR SHALL MAKE ALL POWER CONNECTIONS TO PANEL AND FIXTURES FOR A FULLY OPERABLE SYSTEM. TWO INDIVIDUAL POLE FIXTURES ON TWO SEPERATE INDIVIDUAL CIRCUITS.



MICHAEL MAUST REGISTERED Nº 19600159 STATE OF INDIANA ARCHITECT

GENERAL NOTES

ALTHOUGH DRAWINGS ARE DRAWN TO SCALE, THE ACCURACY OF THE SCALE IS NOT GUARANTEED DUE TO DISCREPANCIES IN THE METHODS OF REPRODUCTION. FIGURED DIMENSIONS SHOULD BE DERIVED FROM DIMENSIONED PLANS.

ALL DIMENSIONS ROUGH OPENING SIZES AND ELEVATION MARKERS MUST BE FIELD VERIFIED BY THE CONTRACTOR PRIOR TO CONSTRUCTION. MAUST ARCHITECTURAL SERVICES SHALL NOT BE HELD RESPONSIBLE FOR ANY DIMENSIONAL DISCREPANCIES WHICH HAVE NOT BEEN BROUGHT TO OUR ATTENTION PRIOR TO CONSTRUCTION.

MAUST ARCHITECTURAL SERVICES DIVISION OF L.E.M., INC.
112 NORTH MAIN STREET
GOSHEN, INDIANA 46526
* Architects
* Planners
* Consultants
* Construction Mgmt.
* Rule 5 and MS4 Filing
PHONE (574) 537-8500
FAX (574) 537-0808

These drawings are the property of Maust Architectural Services and may not be reproduced, copied or reused in any manner without the expressed written consent of Maust Architectural Services.

SSC CONSTRUCTION
Serving Indiana, Illinois, Wisconsin, Michigan, Ohio and Arizona

MERRILLVILLE SCHOOL

8705 MERRILLVILLE RD.
MERRILLVILLE, IN. 46410

REVISIONS:

DATE:

JOB NO.: MAS-17-136

NAME: LIGHTING PLAN

SHEET: E101